



CV. GHANI ABADI

BOQ 3955 Capacitor Bank

No	Item	Merk	Qty	Satuan	Harga Satuan	Jumlah Harga
A. PEKERJAAN PENGADAAN CAPACITOR BANK						
I. Pengadaan Capacitor Bank (Perangkat Utama)						
1	Capacitor Bank Kapasitas 2000 KVAR Compact/Build Up Spain	Ducati 1000-RL	1	Unit	Rp [REDACTED]	[REDACTED]
	- Dilengkapi sistem Auto & Manual					
	- Dilengkapi cooling sistem (Fan & Temperatur Control)					
	- Kapasitas Capacitor 2000 KVAR Pada tegangan 460 Volt					
	- Tegangan Kerja, 380 Volt dapat menahan tegangan pada 460 Volt					
	- Tersedia Space Untuk Reaktor Detuned					
	- Current Transformer Rectangular 1600/5A class 0,2					
II. Material Instalasi						
1	Kabel Capacitor Bank Cell 1,NYY 1x300 mm ²	3,4 besar	30	Meter	Rp [REDACTED]	[REDACTED]
2	Kabel Capacitor Bank Cell 2,NYY 1x300 mm ²	3,4 besar	33	Meter	Rp [REDACTED]	[REDACTED]
3	Kabel Capacitor Bank Cell 3,NYY 1x300mm ²	3,4 besar	39	Meter	Rp [REDACTED]	[REDACTED]
4	Kabel From Panel ACTS 1600A ke Panel I/O Cap.Bank, NYY 1x300 mm ²	3,4 besar	120	Meter	Rp [REDACTED]	[REDACTED]
5	Panel I/O Capacitor Bank	ACB MITSUBISHI	1	Unit	Rp [REDACTED]	[REDACTED]
6	Kabel CT NYMHY 2x1,5mm	3,4 besar	125	Meter	Rp [REDACTED]	[REDACTED]
7	Kabel Ground NYA 1x95mm	3,4 besar	40	Meter	Rp [REDACTED]	[REDACTED]
8	Tray Kabel Leader W600xH100xL3000		3	Btg	Rp [REDACTED]	[REDACTED]
9	Aksesories Tray Kabel (Elbow, Tee, Hanger Beam dll)		1	Set	Rp [REDACTED]	[REDACTED]
10	Aksesories Instalasi :		1	Lot	Rp [REDACTED]	[REDACTED]
	- Skun & Vynil					
	- Kabel Ties					
	- Isolasi Kabel					
	- Fleksibel Kabel					
	- Tie Mount					
	- Dll					
B. JASA INSTALASI CAPACITOR BANK						
I. Mobilisasi Capacitor Bank Baru						
	a. Forklift 5 T , Bongkar Muat Capacitor Bank		1	Lot	Rp [REDACTED]	[REDACTED]
	b. Hand Lift 2T, Positioning Capacitor Bank di Lantai 1					
	c. Hand stecker 1T					
II. Pekerjaan Instalasi						
	a. Pemasangan Kapasitor		1	Lot	Rp [REDACTED]	[REDACTED]
	b. Terminasi dan Konektivitas Pengkabelan					
III. Testing dan Commisioning						
	a. Start up Kapasitor Bank		1	Lot	Rp [REDACTED]	[REDACTED]
	b. Pengetesan System Keseluruhan					
IV. Test dan Reporting						
	a. Pengujian tahanan isolasi instalasi		1	Lot	Rp [REDACTED]	[REDACTED]
	b. Pengujian Continuty Instalasi					
	c. Pembuatan Dokumen IQ OQ					
V. Training Pengoperasian						
	Training Pengoperasian, Perbaikan, Pemeliharaan		1	Lot	Rp [REDACTED]	[REDACTED]
					TOTAL	Rp 2 [REDACTED]